

May 30, 2023

Re: Construction Schedule for TW 2023-01 – N Walworth Road Reconditioning
(Lake Road to CTH F), Town of Walworth

Dear Resident,

Construction for the roadway improvement project on N Walworth Road is tentatively scheduled to begin the week of June 12th and scheduled to be completed by end of September, weather permitting. The schedule provided by the contractor will follow the below sequencing of events:

- Traffic and erosion control
- Ditch grading and culvert installation
- Restoration of disturbed areas (seeding, erosion mat, mulch)
- Pulverize existing asphalt and stabilize roadway
- Pave new roadway asphalt
- Place roadway gravel shoulders
- Place signs and stripe roadway

Any encroachments within the Town of Walworth's roadway right-of-way that conflicts with the proposed construction work shall be removed by the property owner prior to the start of construction. Examples of encroachments are fencing, landscaping, water sprinkler systems, lighting, retaining walls, flagpole, etc. Mailboxes may be temporarily relocated by the contractor, if they conflict with the construction work; however, residents and the post office will be notified prior to any mailboxes being moved.

The contractor is required by the contract to maintain access to driveways and residences unless construction work is immediately adjacent to or through the driveway. We will work to keep residents informed, in advance, of any times that they will not be able to access their driveways, so that vehicles can be moved ahead of time.

Any roads that have construction activities occurring on them will be closed to all thru traffic other than residents. We will be coordinating with emergency services to ensure access for emergency vehicles is maintained.

Should you have any questions, you may contact me by phone 608.365.4464 or email rudzinski@rhbatterman.com.

Very truly yours,



Ryan Rudzinski, P.E.
Project Manager, Batterman – Town of Walworth Engineer

CC: Town Board, Road Superintendent, Town Clerk-Treasurer